

**FINANCIAL BID****Annexure-II**

SN	Description	UOM	Qty	Rate	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum	18		
2	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
	Thermo-Mechanically Treated bars of grade Fe-500D or more.	KG	120		
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centring, shuttering, finishing and reinforcement - All work up to plinth level :				
	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size de rived from natural sources)	Cum	18		
4	Surface dressing on new surface with paving bitumen of grade VG -10 of approved quality using 2.25 kg of bitumen per sqm with 1.65 cum of stone chippings 13.2 mm nominal size per 100 sqm of road surface, including consolidation with road roller of 6 to 8 tonne capacity etc. complete:	Sqm	200		
Total Amount					
Add GST@18%					
Grand Total					