



Annexure - II

PRICE BID

Name of Work: Repair and Kota Stone Work on Trolley Track of Linen Laundry Store, A-Block.

S.N	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer -in - charge				
	Nominal concrete 1:3:6 or richer mix (including equivalent design mix)	Cum	2.5		
2	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement: 4 coarse sand) :				
	25 mm thick	Sqm	22		
3	Brick work with common burnt clay F.P.S. (non-modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				
	Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	3		
4	12 mm cement plaster of mix :				
	1:4 (1 cement: 4 fine sand)	Sqm	15		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	2.5		
TOTAL					

Note:

- Price must be inclusive of all charges like Freight/cartage, loading, unloading and labour charges etc.

SEAL & SIGNATURE OF BIDDER