



Annexure - II

PRICE BID

Name of Work: Repair/Replacement of Damaged Foyer Carbonate Sheet at Right Wing of HIMSR Building.

S.N.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Removing of Existing Polycarbonate Sheet Disposal of material dump out of campus direction by engineer in charge	SQM	95		
2	Supply and Fixing Polycarbonate Sheet 16mm wall 16mm thick of color approved by the Engineer-in-charge. (Including Jointers and Bidding)	SQM	95		
3	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40mm dia M.S. tube 1.5m center to center, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chalis, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevation area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding.	SQM	150		
4	Painting with synthetic enamel paint of approved brand and manufacture of required color to give an even shade: One or more coats on old work.	SQM	81		
5	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	KG	200		
6	Providing and fixing of Aluminum Angle	RM	40		
	TOTAL				
	18% GST				
	GRAND TOTAL				

Note:

- Price must be inclusive of all charges like Freight/cartage, loading, unloading and labour charges etc.

SEAL & SIGNATURE OF BIDDER